
# SITE DEVELOPMENT PLAN

# HOPE VILLAGE INN 201 COUNTY SHED ROAD BURTON BEAUFORT COUNTY, SOUTH CAROLINA



NOT TO SCALE

DATUM: NGVD29 VERTICAL / NAD83 HORZ.

N.P.D.E.S. DISTURBED AREA = 2.7 ACRES

3 DAYS BEFORE DIGGING IN SOUTH CAROLINA CALL 1-888-721-7877 PALMETTO UTILITY PROTECTION SERVICE

# APPROXIMATE LOCATION OF SITE:

LONGITUDE: 80°-44'-28" *LATITUDE:* 32°-26'-80"

# **DEVELOPER NAME:**

JOHN DORTCH
CIRCLE OF HOPE MINISTRIES
P.O. BOX 554
BEAUFORT, SC 29901
(843) 379-9955

# PROJECT DATA INFORMATION:

CIRCLE OF HOPE, BURTON
DISTRICT #: R100
MAP #: 025
PARCEL #: 0328
PROJECT ZONING: T2R ZONING BOUNDARIES: T2R
FEMA FLOOD ZONE: C (CURRENT), X (PRELIMINARY)

# PHONE #:


B.J.W.S.A. 843.987.9250 843.522.3345 O.C.R.M. 843.744.5898 S.C.D.O.T. 843.524.7255 843.525.7712 S.C.E.&G.

# PERMIT#:

\_\_\_\_\_ \_\_\_\_\_ \_\_\_\_\_ PAL. ELEC. 843.208.5512

# APPROVED FOR CONSTRUCTION

# **Ongineering**& Surveying



THE DESIGNS AND IDEAS PRESENTED IN THESE PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

# LEGEND & NOTES SHEET DEMOLITION & EXISTING SITE PLAN OVERALL SITE PLAN

SHEET #

SEDIMENT & EROSION CONTROL PLAN SEDIMENT & EROSION CONTROL DETAILS HORIZONTAL CONTROL PLAN WATERLINE PLAN

INDEX OF DRAWINGS

**DESCRIPTION** 

SANITARY SEWER PLAN & PROFILE DRAINAGE PLAN GRADING PLAN PAVING DETAILS

DRAINAGE DETAILS WATERLINE DETAILS SANITARY SEWER DETAILS PUMP STATION DETAILS

SCDOT SIGHT DISTANCE PLAN TRAFFIC CONTROL PLAN

# DRAWING RELEASED FOR:

\_02\_/\_16\_/\_2022\_ ☑ PLAN REVIEW \_\_\_\_/\_\_\_\_ ☐ PERMIT DRAWINGS ☐ CONSTRUCTION DRAWINGS ☐ BID SET ☐ RECORD DRAWINGS

PLAN REVISIONS				
NO.	DESCRIPTION:	DATE:	BY:	
$\triangle$	-	1	_	
$\triangle$	-	1	_	
3	-	1	_	
<b>A</b>	-	1	_	
$\triangle$	-	1	_	
$\bigcirc$	-	1	_	
$\triangle$		1	_	
À		_		

HOPE VILLAGE INN BJWSA JOB#: 2020-073

# WATER & SANITARY SEWER NOTES

- THE EXISTING WATERLINE INFORMATION HAS BEEN SUPPLIED BY OTHERS. ITS LOCATION AND SIZE ARE APPROXIMATE. THE CONTRACTOR IS TO FIELD VERIFY THE EXACT SIZE AND LOCATION OF THE EXISTING WATERLINE PRIOR TO THE BEGINNING OF CONSTRUCTION.
- THE CONTRACTOR IS TO COORDINATE THE WATERLINE TIE IN WITH BJWSA SEVENTY TWO (72) HOURS MINIMUM BEFORE WATERLINE SHUTDOWN.
- WATERLINES 4" AND ABOVE ARE TO BE C900-DR18-CL150. ALL 2" WATERLINES ARE TO BE HDPE, AND ALL DUCTILE IRON PIPE (DIP) IS
- 4. WATER METERS ARE 2" DIA. UNLESS OTHERWISE NOTED, AND ARE TO BE PROVIDED AND SET BY BJWSA.
- ALL SANITARY SEWER PIPE LENGTHS IN PLAN AND PROFILE VIEWS
- SANITARY SEWER PIPE IS TO BE PVC SDR26.

ARE TO THE CENTERLINE OF THE MANHOLES.

- EXISTING MANHOLE LOCATION, RIM ELEVATION, AND INVERTS HAVE BEEN SUPPLIED BY THE SURVEYOR. THE PIPE LOCATION IS APPROXIMATE AND IS TO BE FIELD VERIFIED BY THE CONTRACTOR IF APPLICABLE.
- SANITARY SEWER LATERALS ARE TO BE LAID WITH A MINIMUM SLOPE OF 0.50% AS SHOWN ON PLANS.
- THE VERTICAL DATUM IS NGVD-29, AND THE HORIZONTAL DATUM IS

BD

BFC

BOC

BS#

BSW

CDK

CLCP

CLCR

CLD

CLP

CLR

CLSW

CMF

CMP

CMS

CO

COGO

COL

CPL

CPP

CRIT

CSW

CTV

EBP

**ECON** 

EDK

EDR

EDW

ECP

ESW

EW

FFE

FOM

GL

GPS#

GRV

GUT

HSB

IPS

**ESTUB** 

TYPICAL ABBREVIATIONS AIR CONDITIONER BOTTOM OF BANK BUILDING CORNER BOTTOM OF DITCH **BENCH** TEMP. BENCHMARK BOTTOM FACE OF CURB BACK OF CURB BACKSIGHT (POINT#) BACK OF SIDEWALK BOTTOM OF WALL CORNER OF ASPHALT CATCH BASIN CORNER OF CONCRETE CORNER OF DECK CORNER OF GRAVEL CURB INLET CENTERLINE OF BIKE PATH CENTERLINE CART PATH CENTERLINE OF CREEK CENTERLINE OF DITCH CLINT CENTERLINE OF INTERSECTION CENTERLINE OF PAVEMENT CENTERLINE OF ROAD CENTERLINE OF SIDEWALK CONCRETE MONUMENT FOUND CORRUGATED METAL PIPE CONCRETE MONUMENT SET CLEAN OUT CALCULATED POINT COLUMN CONTROL PANEL CORNER OF POOL CORRUGATED PLASTIC PIPE S.C. COASTAL CRITICAL LINE CORNER OF SIDEWALK CABLE TELEVISION BOX EDGE OF ASPHALT ELECTRIC BOX

EDGE OF BIKE PATH

EDGE OF CONCRETE

ELECTRIC CONDUIT

EDGE OF DIRT ROAD

EDGE OF DRIVEWAY(DIRT/GRASS)

EDGE OF DECK

EDGE OF GRAVEL

EDGE OF MARSH

ELECTRIC METER

EDGE OF CART PATH

ELECTRIC STUB-OUT

EDGE OF SIDEWALK

EDGE OF WATER

FENCE CORNER

FIRE HYDRANT

FIBER OPTIC MARKER

GPS CONTROL (POINT#)

HANDICAP PARKING STRIPE

IRON PIN CALCULATED(CORNER)

HUB & TACK (POINT#)

IRRIGATION METER

INVERT ELEVATION

IRON PIN FOUND

IRRIGATION VALVE

LANDSCAPE ISLAND

LIGHT POLE/LAMP POST

NORMAL WATER LEVEL

IRON PIN SET

MAIL BOX

MONITOR WELL

FENCE LINE

FLAG POLE

FORESIGHT

GRAVE

GRATE INLET

GUTTER LINE

GAS VALVE

GUY WIRE

HOSE BIB

GROUND LIGHT

FINISHED FLOOR ELEVATION

FENCE

# OVER HEAD WIRE PORCH CORNER

OHP

PK#

PS

PVC

PKS

RCP

SDMH

SLAT

SLM

SSMH

STOP

STP

SUN#

SWB

TIE#

TMH

TOP

**TRNF** 

TSB

TW

UFO

UGG

USS

VCP

WELL

END

SV

RIM

TYPICAL ABBREVIATIONS

POINT OF INTERSECTION P/K NAIL (AS SETUPS) POWER POLE PARKING STRIPE POLYVINYL CHLORIDE PIPE PK NAIL SET REINFORCED CONCRETE PIPE MANHOLE RIM EDGE OF RIP-RAP RADIUS POINT SETBACK STORM DRAIN STORM DRAIN MANHOLE SIGN (THEN A DESC.) SPRINKLER HEAD SEWER LATERAL

SGN"DESC" SEWER LINE MARKER SANITARY SEWER MANHOLE STOP BAR STEP SETUP NAIL# SEWER VALVE

SEWER VALVE MARKER BACK OF SIDEWALK TOPO SHOT (ELEVATION) TOP OF BANK TOP BACK OF CURB TEMPORARY BENCHMARK TELEPHONE PEDESTAL TIE TO SETUP NAIL TREE LINE TELEPHONE MANHOLE TOP OF PIPE TRAVERSE POINT

CONCRETE MARKER . TEMPORARY BENCHMARK CURB INLET TRANSFORMER DRAINAGE MANHOLE (D) TRAFFIC STOP BAR PROP FIRE HYDRANT TOP OF WALL UNDERGROUND CABLE TV WATER VALVE UNDERGROUND ELECTRIC WATER VALVE MARKER WV UNDERGROUND FIBER OPTIC POST INDICATOR VALVE UNDERGROUND GAS LINE MONITORING WELL (M) UNDERGROUND GAS MARKER UNDERGROUND SANITARY SEWER

SANITARY SEWER MANHOLE (S) UNDERGROUND TELEPHONE SANITARY SEWER CLEAN OUT ( UNDERGROUND WATER VERIFIED CLAY PIPE TRANSFORMER WATER WELL EXISTING POWER POLE () WATER FOUNTAIN GUY WIRE → WHITE LINE LIGHT POLE 💢 WATER LATERAL WHITE LINE MARKER AIR CONDITIONER WATER METER

FIBER OPTIC MANHOLE (P) UNDERGROUND GAS MARKER (G) GAS VALVE MAILBOX \_\_\_\_\_\_

DIP CROSSING PROP STORM DRAIN EXISTING STORM DRAIN TOP OF PAVEMENT TOP OF CURB TOP OF SIDEWALK FINISHED GRADE

**EXISTING CONTOUR** 

PROPOSED CONTOUR

∠TP15.50 ∠TC16.00 ∠TS15.25 ∠FG13.50 ———18——— <del>-----(19)-----</del>

# PROJECT REQUIREMENTS FOR HARGRAY TELEPHONE & CATV:

WATER PIPE

WATER TANK

WATER VALVE

YELLOW LINE

**SUFFIXES** 

END (EX. BFC\_END)

ON LINE (EX. BFC\_OL)

WATER VALVE MARKER

- COMMERCIAL BUILDINGS-APARTMENTS-VILLAS TO HAVE A MINIMUM 4" DIAMETER CONDUIT SCH. 40 PVC WITH PULL STRING BURIED AT 24" TO 30" DEPTH, FROM THE EQUIPMENT ROOM OR POWER METER LOCATION TO A POINT DESIGNATED BY HARGRAY AT ROAD RIGHT-OF-WAY OR PROPERTY LINE. CONDUITS ARE REQUIRED FROM EACH BUILDING SITE & MULTIPLE CONDUITS MAY APPLY.
- COMMERCIAL BUILDINGS WITH MULTIPLE "UNITS" MAY REQUIRE CONDUIT(S) MINIMUM 3/4" FROM MAIN EQUIPMENT ENTRY POINT TO TERMINATION POINT INSIDE UNIT. PLENUM TYPE CEILINGS REQUIRE CONDUITS OR FLAME RETARDANT TEFLON WIRING TO COMPLY WITH CODE.
- HOTEL OR LARGE COMMERCIAL PROJECT REQUIREMENTS WOULD BE 2-4" DIAMETER SCH. 40 PVC UNDERGROUND
- 4. EQUIPMENT ROOMS TO HAVE 3/4" 4'X8' SHEET OF PLYWOOD MOUNTED ON WALL TO RECEIVE TELEPHONE EQUIPMENT.
- 5. A POWER GROUND ACCESSIBLE AT EQUIPMENT ROOM OR AN INSULATED #6 FROM THE SERVICE PANEL OR POWER MGN TO THE BACKBOARD.
- 6. RESIDENTIAL WIRING REQUIRES MINIMUM THREE PAIR TWISTED IN LOOP CONFIGURATION (INDUSTRY STANDARD).

7. CATV INSIDE WIRING WILL BE RG6 FOIL WRAPPED 66% BRAID MINIMUM, HOME RUN TO EACH OUTLET.

- 8. ALL INTERIOR WIRING SHOULD BE PULLED TO THE AREA IMMEDIATELY ADJACENT TO THE PLYWOOD BACKBOARD OR
- POWER METER LOCATION. A MINIMUM OF 5' OF SLACK IS REQUIRED FOR TERMINATIONS.
- 9. EASEMENTS ARE REQUIRED.



<u>UTILITY MARKINGS</u> RED - ELECTRIC GREEN - SEWER BLUE - WATER YELLOW - GAS ORANGE - CABLE ORANGE "T"S - TELEPHONE

TYPICAL LEGEND UNLESS OTHERWISE NOTED

allie allie allie

Δ . . Δ . . Δ . . Δ

EDGE OF GRAVEL EG

BOTTOM OF BANK BB

×8.43

IRON PIN

SIGNAL BOX 8

GRATE INLET

CATCH BASIN

EXIST FIRE HYDRANT

IRRIGATION VALVE (()

IRRIGATION METER ⊗

WATER METER  $\bigoplus$ 

HOSE BIB ⊕

SEWER VALVE

CABLE TV BOX

FIRE DEPT CONNECTOR

TELEPHONE PEDESTAL T

ELECTRIC BOX (ELEC.)

DRAINAGE ARROWS

GROUND LIGHT

FLAG POLE or

WETLANDS

LAGOON/POND

EX. ASPHALT

EX. CONCRETE

DEMO ASPHALT

DEMO CONCRETE

EX. CRUSHED AGGREGATE

DEMO CRUSHED AGGREGATE

HD ASPHALT PAVEMENT

MD ASPHALT PAVEMENT

PERVIOUS CONCRETE PAVEMENT

STONE RIP-RAP ON ENG FABRIC

FUT. PERVIOUS CONCRETE PAVEMENT

CONCRETE PAVEMENT

CRUSHED AGGREGATE

FUT. ASPHALT PAVEMENT

FUT. CONCRETE PAVEMENT

FUT. CRUSHED AGGREGATE

EDGE OF PAVEMENT EP

EXISTING SPOT ELEVATION

TOP OF BANK TB

LANDSCAPE AREA

- NO SITE WORK SHALL BEGIN ON A REGULATED SITE UNTIL THE OCRM LAND DISTURBANCE PLACARD IS POSTED ON SITE, ALL TREE PROTECTION IS IN PLACE AND ALL REQUIRED SILT FENCE
- 2. A HORIZONTAL & VERTICAL CONTROL MONUMENT HAS BEEN DESIGNATED BY THE ENGINEER. THE VERTICAL DATUM IS NGVD-29, AND THE HORIZONTAL DATUM IS NAD 83.
- 3. ALL PAVEMENT DIMENSIONS (i.e.; ROAD WIDTHS, PARKING LOTS, LANDSCAPE ISLANDS, etc.) ARE GIVEN TO THE EDGE OF PAVEMENT OR BACK OF CURB, AS SITE DICTATES.
- 4. ALL BUILDING TIES ARE PERPENDICULAR TO THE PROPERTY LINES.
- 5. CONTRACTOR TO IDENTIFY AND LOCATE ALL UNDERGROUND UTILITIES PRIOR TO STARTING CONSTRUCTION.
- CONTRACTOR RESPONSIBLE FOR TRAFFIC CONTROL AND SAFETY DURING CONSTRUCTION. CONTRACTOR RESPONSIBLE FOR SECURING SITE DURING NON-WORKING HOURS TO ENSURE
- 8. THE GENERAL CONTRACTOR AND SUB-CONTRACTORS SHALL BE AWARE THAT SOME PART OR ALL OF THE CONSTRUCTION OF THIS SITE MAY FALL UNDER THE JURISDICTION OF SPECIFIC CONDITIONS RELEVANT TO A SCDOT OR BEAUFORT COUNTY ENCROACHMENT PERMIT. UNITED STATES ARMY CORPS PERMIT, SETBACKS/BUFFERS PERTINENT TO THE ESTABLISHED ZONING ORDINANCES, SC-DHEC PERMITS, DHEC-OCRM PERMITS OR THE WATER AND SEWER AUTHORITY OF JURISDICTION. IT SHALL BE THE CONTRACTOR'S SOLE RESPONSIBILITY TO CONFIRM THE EXISTENCE AND CONDITIONS OF ALL PERMITS RELEVANT TO THIS PROJECT PRIOR TO THE
- COMMENCEMENT OF THE IMPACTED PHASE(S) OF CONSTRUCTION. ). CONTRACTOR IS MADE AWARE THAT OSHA REQUIRES A PROTECTIVE SYSTEM DESIGNED BY A REGISTERED PROFESSIONAL ENGINEER FOR EXCAVATIONS DEEPER THAN 20 FT.
- 10. CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO EXISTING
- ROADWAYS FROM CONSTRUCTION AREAS. 11. TEMPORARY CONTROL OF STORM WATER DRAINAGE SHALL BE THE RESPONSIBILITY OF THE
- GENERAL CONTRACTOR, AND SHALL BE MAINTAINED THROUGHOUT THE PERIOD OF CONSTRUCTION. 12. WHERE EXISTING PAVEMENT IS SHOWN TO BE MATCHED, THE EDGE OR CONTACT FACE WITH THE EXISTING PAVEMENT SHALL BE SAW CUT (A CLEAN EDGE) 1' INTO EXISTING PAVEMENT TO AVOID THE NEW PAVEMENT SEAM FROM MATCHING THE OLD BASE/NEW BASE JOINT.
- 13. ALL TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF: SOUTH CAROLINA DEPARTMENT OF HIGHWAYS AND PUBLIC TRANSPORTATION. THE SOUTH CAROLINA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS

# SEDIMENT & EROSION CONTROL NOTES:

TRAFFIC AND PEDESTRIAN SAFETY.

- . IF NECESSARY, SLOPES, WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.
- STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED. BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW. WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS
- WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.
- ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY CALENDAR WEEK. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY OR INCORRECTLY INSTALLED, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN 48 HOURS OF IDENTIFICATION.
- 4. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE SEDIMENT BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.
- 5. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE
- THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.
- 8. RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE AS WELL AS FOR INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH S.C REG. 72-300 ET SEQ. AND SCR100000.
- 9. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.
- 10. ALL WATERS OF THE STATE (WOS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WOS. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WOS.
- 11. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.
- 12. A COPY OF THE SWPPP, INSPECTIONS RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.
- 13. INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:1V OR GREATER) WHERE LAND-DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS.
- 14. MINIMIZE SOIL COMPACTION AND, UNLESS INFEASIBLE, PRESERVE TOPSOIL.
- 15. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE;
- 16. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMPS (SEDIMENT BASIN, FILTER BAG, ETC.).
- 17. THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED: WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE
- WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM RELEASE OILS,
- CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS; • FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND
- MAINTENANCE: AND • SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING.
- 18. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
- 19. IF EXISTING BMPS NEED TO BE MODIFIED OR IF ADDITIONAL BMPS ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND/OR SC'S WATER QUALITY STANDARDS. IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE. IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE, THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPS MUST BE IMPLEMENTED AS SOON AS REASONABLY POSSIBLE.
- 20. A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB 10 ACRES OR MORE THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT HAS APPROVED OTHERWISE.

## CONSTRUCTION SEQUENCE

- RECEIVE NPDES COVERAGE FROM DHEC
- PRE-CONSTRUCTION MEETING
- 3. NOTIFY DHEC EQC REGIONAL OFFICE OR OCRM 48 HOURS PRIOR TO BEGINNING LAND-DISTURBING ACTIVITIES
- 4. INSTALLATION OF CONSTRUCTION ENTRANCE(S)
- 5. CLEARING & GRUBBING ONLY AS NECESSARY FOR INSTALLATION OF PERIMETER CONTROLS
- 7. CLEARING & GRUBBING ONLY IN AREAS OF BASIN/TRAPS/PONDS

6. INSTALLATION OF PERIMETER CONTROLS (E.G., SILT FENCE)

- INSTALLATION OF BASINS/TRAPS/PONDS AND INSTALLATION OF DIVERSIONS TO THOSE STRUCTURES (OUTLET STRUCTURES MUST BE CÓMPLETÉLY INSTALLED AS SHOWN ON THE DETAILS BEFORE PROCEEDING TO NEXT STEP: AREAS DRAINING TO THESE STRUCTURES CANNOT BE DISTURBED UNTIL THE STRUCTURES AND DIVERSIONS TO THE STRUCTURES ARE COMPLETELY INSTALLED)
- CLEARING & GRUBBING OF SITE OR DEMOLITION (SEDIMENT & EROSION CONTROL MEASURES FOR THESE AREAS MUST ALREADY BE INSTALLED)
- 11. INSTALLATION OF STORM DRAIN SYSTEM AND PLACEMENT OF INLET PROTECTION AS EACH INLET IS INSTALLED
- 12. FINE GRADING, PAVING, ETC.

10. ROUGH GRADING

- 13. PERMANENT/ FINAL STABILIZATION
- 14. CLEAN-OUT OF DETENTION BASINS THAT WERE USED AS SEDIMENT CONTROL STRUCTURES AND RE-GRADING OF DETENTION POND BOTTOMS: IF NECESSARY, MODIFICATION OF SEDIMENT BASIN RISER TO CONVERT TO DETENTION
- 15. REMOVAL OF TEMPORARY SEDIMENT & EROSION CONTROL MEASURES AFTER ENTIRE AREA DRAINING TO THE STRUCTURE IS FINALLY STABILIZED (THE DEPARTMENT RECOMMENDS THAT THE PROJECT OWNER/OPERATOR HAVE THE SWPPP PREPARER OR REGISTRATION EQUIVALENT APPROVE THE REMOVAL OF TEMPORARY STRUCTURES)
- 16. PERFORM AS-BUILT SURVEYS OF ALL DETENTION STRUCTURES AND SUBMIT TO DHEC OR MS4 FOR ACCEPTANCE
- 17. SUBMIT NOTICE OF TERMINATION (NOT) TO DHEC AS APPROPRIATE

# TRAFFIC SIGNS AND MARKERS NOTES:

- ALL EXISTING SIGNS NOT SPECIFIED TO BE RELOCATED ARE TO BE RETURNED TO BEAUFORT COUNTY TRAFFIC ENGINEERING UPON REMOVAL
- NOTIFY BEAUFORT COUNTY TRAFFIC ENGINEERING WHEN THE PROJECT IS SUBSTANTIALLY COMPLETE TO ALLOW INVENTORY OF SIGNING AND PAVEMENT MARKINGS.

# DEMOLITION NOTES:

- CONTRACTOR TO ENSURE ALL SEDIMENT AND EROSION CONTROL MEASURES ARE INSTALLED PRIOR TO PERFORMING DEMOLITION.
- WHEN REMOVING EXISTING CULVERT PIPES. CONTRACTOR TO REPAIR DRIVEWAY TO

MAINTAIN ACCESS TO PROPERTY.

# UTILITY NOTES:

- SHOWN ON PLAN ARE KNOWN UNDERGROUND UTILITY LOCATIONS, HOWEVER, NOT SHOWN BUT POSSIBLY ENCOUNTERED IN THE AREA OF THE SITE ARE OTHER BURIED UTILITIES INCLUDING,
- BUT NOT NECESSARILY LIMITED TO; A TELEPHONE
- FIBER OPTICS CABLE TELEVISION POTABLE WATER
- SANITARY SEWER GAS PIPELINE / TRANSMISSION LINE . STORM SEWER (NOTE: ALL UTILITIES ENCOUNTERED TO BE
- PROTECTED DURING CONSTRUCTION) CONTRACTOR RESPONSIBLE FOR CONTACTING NECESSARY UTILITY COMPANIES AND
- COORDINATING UTILITY RELOCATES AS SHOWN ON SITE PLANS WHEN ENCOUNTERED, THE CONTRACTOR SHALL PROVIDE THE ENGINEER WITH WRITTEN GRAPHICAL INFORMATION PERTAINING TO THE VERTICAL & HORIZONTAL ALIGNMENT OF UTILITY LOCATIONS BEFORE PROCEEDING WITH CONSTRUCTION.
- THE COST ASSOCIATED WITH THE LOCATING AND RELOCATING OF UTILITIES WILL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- FOR UTILITIES ENCOUNTERED BUT NOT SHOWN ON PLANS, THE CONTRACTOR'S COST WILL BE BASED ON THE UNIT BID PRICE OR A NEGOTIATED FEE.

# Storm sewer notes:

- RCP IS TO BE (CLIII). UNLESS OTHERWISE
- HDPE IS TO BE N-12 UNLESS OTHERWISE
- ALL PIPE LENGTHS IN THE PLAN AND PROFILE VIEWS ARE TO THE INSIDE EDGE OF THE STRUCTURE ALONG THE CENTERLINE OF THE
- PIPE. FOR REFERENCE PURPOSES ONLY. SUBGRADE DRAIN IS TO BE 4" PERFORATED
- WRAP ALL JOINTS W/GEOTEXTILE FABRIC
- . COMCAST
- 4400 BELLE OAKS DR. N. CHARLESTON, SC 29405

WITH GEOTEXTILE SOCK.

- (843) 266-3010 . DÒMINÍON ENERGY SOUTH CAROLINA TERRENCE HARRIS
- PO BOX 1168 BEAUFORT, SC 29901 (843) 525-7731 CENTURY LINK
- DAVID STILES PO DRAWER 1659 BEAUFORT, SC 29902 (843)-525-7979)
- . HARGRAY COMMUNICATIONS GROUP, INC. DEBORAH COOLER PO BOX 346 BLUFFTON, SC 29910 (843) 683-1687
- DICK DEUEL 6 SNAKE RD. OKATIE, SC 29909 987-9251

F:\Projects\2019\2019 Projects\190034 Circle of Hope Burton\DWG\190034\_cov.dwg

B

Site Development Plan

Hope Village Inn 201 County Shed Road Burton

Beaufort County, SC


Legend & Notes Sheet


Date Drawn: 08/21/19 02/05/21 Last Revised: Drawn By: L. Wilen

SHEET #

Engineer:

A. Klosterman





THE DESIGNS AND IDEAS PRESENTED IN THESE DRAWINGS ARE THE COPYRIGHTED PROPERTY OF ANDREWS ENGINEERING CO., INC. THE USE OR REPRODUCTION OF THESE PLANS OR THEIR CONTENT IS STRICTLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.	S S S S S S S S S S S S S S S S S S S		
THE DESIGNS AND IDEADRANNGS ARE THE COPYRIGENGINEERING CO., INC. THOM THESE PLANS OR THESE PLANS OR THESE WITHOUT F	ANDREWS ANDREWS ANDREWS NO. CO0008		

Site Development Plan Hope Village Inn 201 County Shed Road Burton Beaufort County, SC

> Demolition & Existing Site Plan

Date Drawn: 08/21/19 Last Revised: 02/05/21 L. Wilen Drawn By: A. Klosterman

